



2016 Jaffrey Road Reconstruction and Paving Projects

Paving work tentatively scheduled to begin Thursday May 19th

1. **Gilmore Pond Road:** Beginning from Great Road and proceeding east for approximately 1,500 feet – 2” paving overlay
2. **Crestview Dive:** Beginning from North Street (Route 137) and proceeding approximately 1,200 feet – 2” paving overlay (section that was not done last year)

Road and drainage reconstruction work to be scheduled

1. **Nutting Road:** Beginning from Pole 143 and proceeding east approximately 1,360 feet – reclaim and add 2” base pavement and 1” overlay
2. **Fitzwilliam Road:** Beginning from Great Road and proceeding to Old County Road – reclaim and add 2” base pavement and 1” overlay
3. **Gilmore Pond Road:** Beginning east of Sandy Lane and proceeding west approximately 1,500 feet to Pole #14 – reclaim and add 2” base pavement and 1” overlay
4. **Thorndike Pond Road:** Fine grading of approximately 1,420 feet of existing gravel road between Poles #34 and #4, drainage improvements and adding 2” base pavement and 1” overlay

